

john lark and associates  
architects and planners  
8739 big bend blvd  
st. louis, missouri 63119  
[www.jla-arch.com](http://www.jla-arch.com)

(314) 968-2888  
fax : (314) 968-3248  
email: postmaster@jla-arch.com

---

**ADDENDUM NO. 3**

**pages 2**

---

**Date:** May 21, 2010

**Project:** Shop 'N Save – O'Fallon

The following additions, revisions, clarifications and corrections are to be incorporated into the plans and specifications dated May 3, 2010, for a proposed Shop 'N Save Supermarket, and are to be included in the bids for this project:

**NOTE:** This Addendum includes responses to RFI's submitted over the last 2 days. It is being sent to all Contractors for clarification because RFI's have been both forwarded directly to us and submitted through Procom. NO DRAWING CHANGES ARE BEING MADE AT THIS TIME WITH THIS ADDENDUM:

1. The Stanley Automatic Doors AND Transom are to be supplied to the job including glass glazing.
2. The Vinyl wall covering in the sales area to to be supplied and installed by the décor contractor under separate contract.
3. Specification Section 08410 Aluminum Storefronts 1.3B does not apply. Provide only standard shop drawings as specified under 1.3 A.
4. Follow wall type designations for 1/2 inch drywall throughout rather than any details that indicate 5/8" drywall.
5. The ceiling in the Pharmacy is to be 9'-0" AFF.
6. The Room Finish Schedule, Sheet A6.1 incorrectly indicates an Acoustical Tile Ceiling in the Checkout Area, Room 107. This area is open bar joists and roof deck, finished the same as the Sales Area, Room 100. The Ceiling Plan, Sheet A4.3 is correct.
7. The plastic Laminate in the Toilet Rooms 109 and 110 should be Nevamar "Straw Matrix" Textured #MR2006T.
8. Please refer to the drawings for the Laminate Glass selection, Exterior Finish Schedule, Sheet A2.1. The spec lists a number of Laminate Glass types that do not apply, only Type A and B apply to this project.

9. Clarification for Sheet S-2:

- The Type 3 Base Plate should be 7/8" thick.
- Columns shown on the Roof Framing Plan, south and west of Col 7 near Col C.1 are the mezzanine columns below, shown light on the Framing Plan and designated on the Mezzanine Framing Plan to the right on the sheet.

10. Testing and Balancing of the HVAC System is provided by SNS under separate contract as noted in the spec.

11. The Sprinkler Criteria Plan, Sheet SP-1 Clarification:

- Note that the exterior Produce Prep and Coolers to the left of Col Line 1 should be supplied by an anti-freeze system off of the wet sprinkler. These are exterior cooler units and the anti-freeze system should penetrate the cooler walls and include upright heads on exposed lines in these areas. All lines in the coolers are to be painted.

12. The Mitsubishi Split System, Unit CU-1 and AC-1 are to be supplied by SNS, installed by the GC under this contract the same as the other HVAC Equipment.

13. There was a question regarding the rear stock area increased density note, referencing NFPA Section 7.3. Previous sections applicable to this condition were under NFPA 7.3, however the most recent NFPA 13 - 2010 edition has moved this provision to 14.2.4.5. The note as indicated still applies.

This Concludes Addendum No.3